



A Z U M A
Design

Laboratory Report

Date

26-August-2011

Customer ALUPLAST GmbH

Kunststoffprofile, Auf der Breit 2, D-76227 Karlsruhe

Test No :

AZT0146.11.xls



NATA Accredited Laboratory No : 15147

Azuma Design Pty Limited
160 Newton Rd Wetherill Park. NSW 2164 Ph 02 9604 0255 E-Mail info@azumadesign.com.au

This document is issued in accordance with NATA's accreditation requirements.
Accredited for compliance with ISO/IEC 17025.

This document shall not be reproduced, except in full.

AZUMA DESIGN

TESTING LABORATORY REPORT



SIGNATORIES	Reported by: Nathan Olsen <i>[Signature]</i>
	Checked by: Robert Irwin <i>[Signature]</i>

Date :	26-Aug-11
	Test No:
AZT0146.11.xls	

NATA Accredited Laboratory No : 15147

Wind and Water Penetration Testing

Testing to AS 2047.1 as per test method 4420.0 to .6

Manufacturer / Customer ALUPLAST GmbH

Test Sample Data Deflection Ratio 1
180

Unit type	Sliding/Fixed Window	
Unit code	60mm Sliding Window	
Size	H (mm)	1200
	W (mm)	2500
Design Pa:	1500	

Tested For	Y / N	Rating	Units
Structural Deflection ?	Yes	1500	Pa
Air Infiltration ?	Yes	75/150	Pa
Operating Force Initial / constant ?	Yes	90/110	N
Water Penetration ?	Yes	150	Pa
Ultimate Strength ?	Yes	3300	Pa

Test Unit Specifications

Results

Sizes		H	W	Area sq m	Glass Type	Structural Framing Member	Span (mm)	Allowable Deflection	Deflection Result	Actual Ratio	Test Press (Pa)	Results
Frame		1200	2500	3.00		Interlock P	1025	5.69	2.14	479	1500	P
Sash	Sliding	1085	1225	1.33		Interlock N	1025	5.69	2.69	381	1500	P
	Fixed	1085	1225	1.33		Mullion P						
						Mullion N						
Glass	Thickness (mm)	H	W			Transom P						
	Sliding	4,12,4	970	1113	1.08	Clear Float	Transom N					
	Fixed	4,12,4	970	1113	1.08	Clear Float	H/L Trans P					
							H/L Trans N					
							H/L Mullion P					
						H/L Mullion N						
						Meet Style P						
						Meet Style N						
						Spare						
						Spare						

AZUMA DESIGN

TESTING LABORATORY REPORT

Test equipments

The test equipment and methods used in the above test comply with the requirements of AS 4420.1-6.

Test Specimen

See drawings at the end of this report.

Test Methods

The test unit was fixed into the rig as outlined in AS 4420.1.

Deflection Test

The unit was subjected to both positive and Negative pressure as prescribed in AS 4420.2. After the initial settling in of the unit at the 50% of the required test pressure, the differential pressure was then applied slowly until the nominated design pressure was reached in Positive. This process was then repeated for the Negative.

Results of Test

The test unit satisfied the requirements of AS 2047.1 in both the positive and negative deflection at the nominated design pressure.

Observations

NIL

Air Infiltration Test

The test was first completely sealed against air leakage as per AS 4420.4 to determine the air leakage of the test rig. It was then subjected to 75 Pa of both positive and negative pressure, and 150 Pa of both negative and positive pressure. Differential pressures were recorded. The test unit was then unsealed and subjected to 75 Pa of both positive and negative pressure. Differential pressures were recorded and air leakage then calculated. The actual leakage of the test unit was then determined.

Barometric pressure (Pbar):	1018	Air temperature (°C)	20	
Max Pressure (Pa)	SEALED		UNSEALED	
	Positive (Pa)	Negative (Pa)	Positive (Pa)	Negative (Pa)
75	13	10	21	21
150	32	28	56	63

Test Pressure	Pressure Direction	Building / Window Type	Allowable leakage flow L/s m ²	Test results			
				Is ⁻¹ m ⁻² Positive	Is ⁻¹ m ⁻² Negative	Pos +	Neg -
75 Pa	+/-	Air conditioned	1.0	0.30	0.44	Passed	Passed
75 Pa	+	Non air conditioned	5.0	0.30	0.44	Passed	
150 Pa	+/-	Air conditioned	1.6	0.56	0.81	Passed	Passed
150 Pa	+	Non air conditioned	8.0	0.56	0.81	Passed	

AZUMA DESIGN

TESTING LABORATORY REPORT

Results of test

The test unit satisfied the requirement of AS 2047. The test unit was tested to AS 4420.4. The net flow readings are as follows:

Observation

NIL

Operating Force

OPERATING FORCE (N)

		Opening Force	Closing Force
Initiating Movement	Sash 1	55	26
Sustaining Movement	Sash 1	15	16
Initiating Movement	Sash 2		
Sustaining Movement	Sash 2		
Initiating Movement	Sash 3		
Sustaining Movement	Sash 3		

A force gauge was attached to the operating handle of the sash to determine the force required to set the sash in motion and thereafter to maintain motion as per AS 4420.3.

Results of test

The test unit satisfied the requirement of AS 2047.

Observations

NIL

AZUMA DESIGN

TESTING LABORATORY REPORT

WATER PENETRATION

Water was applied to the exterior of the test unit with no less than 0.05 ls-1m-2 for a period of five minutes at zero pressure. After five minutes, a nominated pressure was applied for fifteen minutes as per AS 4420.5.

Maximum pressure (Pa) applied for 15 minutes (Nominated pressure)

150

Results of test

The test unit satisfied the requirement of AS 2047 in positive pressure at the nominated design pressure.

Observations

NIL

ULTIMATE STRENGTH TEST

A pressure nominated on part 1 of this report and determined by AS 2047, table 2.5 was applied to the test unit for a period of 10 seconds as per AS 4420.6.

Max. pressure reached for 10 seconds	
Positive	Negative
3300	3300


Results of test :	Y or N
Dislodgement of any glass?	No
Dislodgement of a frame or any part of a frame?	No
Removal of alignment with or without its framing sash from a frame?	No
Loss of support of a frame such as when it is unstable in its opening in the building structure?	No
Failure of any sash, locking device, fasteners or supporting stay which would allow an opening light to come open?	No
The test unit satisfied the requirement of AS 2047.	

Observations

NIL

Sliding-Window SF60 Schema A

Position 4
Maßstab: ~
Datum: 2011-08




NATA Accredited Laboratory
Number: 15147

This laboratory is accredited by the National Association of Testing Authorities, Australia. The tests reported herein have been performed in accordance with its scope of accreditation. This document shall not be reproduced, except in full.


Checked by: *[Signature]*

Hardware: Roto



**Sliding-Sash
Cross-sektion 3-4**

**Sliding-Sash
Cross-sektion 1-2**



Drainage
Frame
Sliding+ Fix Sash

